






APPLICABLE FIELD MEMBRANES

TPO REINFORCED
TPO FLEECE BACK
TPO SELF-ADHERING

7



- 1 THE HOLE SHALL BE AT LEAST THE SAME DIAMETER AS THE DRAIN PIPE.
- 2 THE MEMBRANE MUST BE NO LESS THAN 1/2" FROM THE ATTACHMENT POINTS OF THE DRAIN CLAMPING RING.
- 3 ALL BOLTS AND CLAMPS MUST BE IN PLACE TO PROVIDE CONSTANT COMPRESSION ON THE WATER CUT-OFF MASTIC.
- 4 ENSURE THE DRAIN RING IS COMPLETELY CLEAN DOWN TO BARE METAL.
- 5 APPROX. 1/8" BEAD OF CUT-EDGE SEALANT IS REQUIRED ON CUT EDGES OF TPO REINFORCED MEMBRANE.
- 6 IF THE SLOPE IN THE DRAIN SUMP EXCEEDS 3":12", THEN DIVIDE THE TPO REINFORCED MEMBRANE TARGET PATCH INTO SECTIONS PER DETAIL **TP-DR-C402**.
- 7 TPO FLEECE BACK MECHANICALLY ATTACHED SYSTEMS REQUIRE FASTENERS IN PLATES IN CONJUNCTION WITH THE TARGET PATCH. REFER TO DETAIL **TP-DR-A407**.

APPLICABLE FIELD MEMBRANE (AND SYSTEMS)

TPO REINFORCED (ADHERED) (MECHANICALLY ATTACHED) (INDUCTION WELDED)
TPO FLEECE BACK (ADHERED) (MECHANICALLY ATTACHED: 20 YR MAX)
TPO SELF-ADHERING (ADHERED)

MULEHIDE

TPO DRAIN FLASHING: FOR USE WITH ANY TPO FIELD MEMBRANE

WHEN THE SYSTEM TYPE AND PROJECT DESIGN PERMIT, THIS DETAIL IS
ACCEPTABLE FOR : **MAXIMUM 30 YEAR WARRANTY**

DETAIL NO.:

TP-DR-C401

REVISION DATE: 8/24/2026