





- 1** A MINIMUM OF 4 MULEHIDE APPROVED FASTENERS AND PLATES ARE REQUIRED ON MECHANICALLY ATTACHED AND INDUCTION WELDED SYSTEMS. FASTENERS AND PLATES MAYBE PLACED INSIDE THE BOOT, SO AS LONG THE PLATES DO NOT INTERSECT THE BOOT FLANGE. OTHERWISE THEY MUST BE PLACED OUTSIDE THE BOOT FLANGE A MAXIMUM OF 12" O.C. FROM THE PIPE AND SPACED 12" O.C. MAXIMUM. REFER TO DETAIL **TP-PP-C518** FOR FLASHING REQUIREMENTS WHEN FASTENERS AND PLATES ARE PLACED OUTSIDE THE FLANGE.
- 2** TEMPERATURE OF THE PIPE PENETRATION MUST NOT EXCEED 160°F.
- 3** REMOVE ALL LEAD OR OTHER FLASHING BEFORE INSTALLING THE PRE-MOLDED PIPE BOOT.

APPLICABLE FIELD MEMBRANE (AND SYSTEMS)
 TPO REINFORCED (ADHERED) (MECHANICALLY ATTACHED) (INDUCTION WELDED)
 TPO FLEECE BACK (ADHERED) (MECHANICALLY ATTACHED: 20 YR MAX)
 TPO SELF-ADHERING (ADHERED)

MULEHIDE

TPO PIPE SEAL

DETAIL NO.:
TP-PP-C503

WHEN THE SYSTEM TYPE AND PROJECT DESIGN PERMIT, THIS DETAIL IS
ACCEPTABLE FOR : **MAXIMUM 30 YEAR WARRANTY**

REVISION DATE: 8/24/2026