


Summary Specification

"The name trusted in roofing since 1906"



APP TORCH

20 – Year Material or System Warranty Concrete Deck



Deck Requirement
3000 psi Concrete ⁽¹⁾

Insulation
• None

Base Sheet ⁽⁴⁾
• App Torch Base
• SA Base ^{(2), (3)}
• SA Base FR ^{(2), (3)}

Cap Sheet
• APP Torch G
• APP Torch G FR

Slope Requirement
¼" per foot

Notes:

1. Concrete deck must be primed with #121 Asphalt Primer at a rate of ¼ gal per 100 square feet.
2. APP Torch may be applied directly over SA Base or SA Base Fr.
3. If SA Base is used, ambient temperatures must be 50° F and rising.
4. Two interply layers of approved Base Sheet are required.
5. Flashings are to be one interply Base Sheet and one Cap Sheet installed in accordance with Mule-Hide Standard Details.

PRODUCTS NOT SUPPLIED BY MULE-HIDE PRODUCTS ARE NOT COVERED UNDER THE MULE-HIDE WARRANTY

PLEASE CONSULT THE MULE-HIDE WEBSITE FOR THE MOST CURRENT INFORMATION AT WWW.MULEHIDE.COM