


NOTES:

1. THE MEMBRANE MUST BE SPECIFIED WITH PERIMETER ENHANCEMENT INSTALLED OVER THE ENTIRE OVERHANG AREA. WHEN THE OVERHANG IS AT THE SAME LEVEL AS THE MAIN ROOF, EXTEND THE PERIMETER ENHANCEMENT ONTO THE MAIN ROOF LEVEL AS SHOWN.
2. AS AN OPTION, AN ADHERED MEMBRANE SECTION MAY BE USED IN LIEU OF THE MECHANICALLY FASTENED MEMBRANE AT BUILDING OVERHANGS IN ACCORDANCE WITH THE MULE-HIDE FULLY ADHERED TPO ROOF SYSTEM SPECIFICATION.
3. REFER TO TECHNICAL BULLETIN #TPO-MA02-2006 FOR PERIMETER ENHANCEMENT REQUIREMENTS.



INSTALL APPROVED PERIMETER ENHANCEMENT OVER THE ENTIRE OVERHANG AREA - SEE NOTE 1

PERIMETER ENHANCEMENT

**MULE-HIDE  
PRODUCTS CO., INC.**

**SHEET LAYOUT ON BUILDINGS  
WITH OVERHANGS**

**SYSTEMS:**

**MECHANICALLY ATTACHED**

**DETAIL NO.:**

**MHT-MA-103B**

REVISION DATE: 10/2013